

1200 Prairie Dr SW Bondurant, IA 50035 Phone: 515-263-8900 ~ Fax: 515-265-7750 www.JPettiecord.com

| TO: | City of Ankeny | PROJECT NAME: | Deer Creek Truck Sewer | |
|----------|---------------------------|---------------|------------------------|--|
| | | | Extension Clearing and | |
| | | | Grubbing | |
| ADDRESS: | | LOCATION: | Deer Creek Development | |
| | | | NE Side of Ankeny | |
| ATTN: | Gary Reed w/ CDA | ENGINEER: | CDA | |
| PHONE: | | PLAN DATE: | 2-1-18 | |
| FAX: | | LAST REVISED: | | |
| DATE: | February 20, 2018 revised | ADDENDUMS: | | |
| FROM: | Nick Wylie | , N | | |

Scope of work will include:

- 1. Tree removal and disposal for Deer Creek Trunk Sewer Project. Includes grinding the trees and incorporating the wood chips into the topsoil 100 feet from the creek.
- 2. Installation of creek crossings for the Deer Creek Truck Sewer Project. This includes a 20' long 30" diameter pipe in each crossing and some rip rap on the upstream side.
- 3. Tree removal and disposal for Deer Creek Box Culvert Project. Includes grinding the trees and incorporating the wood chips into the topsoil 100 feet from the creek.

| <u>Item</u> | <u>Description</u> | <u>Unit</u> | QTY | Unit Price | Total |
|-------------|--------------------------------------|-------------|-----|-------------|-------------|
| 1 | Tree Clearing for Trunk Sewer Line | LS | 1 | \$23,000.00 | \$23,000.00 |
| 2 | Creek Crossings for Truck Sewer Line | LS | 1 | \$8,600.00 | \$8,600.00 |
| 3 | Tree Clearing for Box Culvert | LS | 1 | \$23,000.00 | \$23,000.00 |
| | Total | | \$ | | \$54,600.00 |

Note:

- Clearing limits will be marked clearly by the civil engineer.
- If any trees are to stay within the clearing limits and then have to be taken out after we are gone, then the cost to remove them plus mobilization will be assessed to the final invoice.
- Cleanup will be done by a root rake which will get most of the roots and limbs.

Excludes:

Erosion control measures and SWPPP Development and Implementation, survey, tree protection measures, tree trimming, marking of trees to be saved, traffic control, issues with endangered species, mowing, bonds, backfill, permits, railroad insurance policies and flaggers, additional mobilizations, removal of fence, trash, rubble, debris, and dirt with brush mixed in.

| Accepted by: | Contractor: 3 | I. Pettiecord, Inc. |
|--------------|---------------|---------------------|
| | | 422 |

^{*24} Hour Spill Response * Tree Clearing * Environmental Construction and Remediation *

^{*} Excavating * Heavy Hauling * Dump Trucking * Demolition * Asbestos Removal *